


Republic of the Philippines
ILOILO SCIENCE AND TECHNOLOGY UNIVERSITY

La Paz, Iloilo City

• Trunkline: (033)320-7190 • Telefax: (033)329-4274
 • Website: www.isatu.edu.ph



Section VI. Schedule of Requirements

The delivery schedule expressed as weeks/months stipulates hereafter a delivery date which is the date of delivery to the project site.

Item Number	Description	Quantity	Total	Delivered, Weeks/Months
1	Managed Switch 24 PoE ports loaded with 4 Transceivers	6		30 days
2	Managed Switch 24 PoE ports loaded with 2 Transceivers	16		
3	Managed Switch 8 PoE ports loaded with 2 Transceivers	19		
4	Uninterruptible Power Supply 650VA	42		
5	UTP Cable CAT 6 305m/box	8		
6	Rack Cabinet 2 ft 19" Lockable with 4 outlets 3 prong 220V power strip, flexi-glass front door with push lock, detachable vented side panels	38		
7	Server Rack Enclosure 42U Standard 19" cooling fan, 14 outlets 3 prong 220V power strip, 2 unit vertical cable manager at the side front	7		
8	Fabricated, Pre-terminated UTP CAT6 (AWG23) patch cable, 2m	500		
9	Patch Panel, 24-port CAT6	50		
10	Wire Manager 1U, 19"	60		
11	KVM 8-port bundle with monitor/keyboard, 8 cables	4		
12	KVM 16-port bundle with monitor/keyboard, 16 cables	1		
13	Information Outlet CAT6	450		
14	2-gang Faceplate for I/O with box	250		
15	Fiber cable 8-core, Single-mode, Outdoor	300		
16	12-port 19" Optical Distribution Frame, 1U, loaded with 8 LC pigtails, 8 LC-LC adaptors	42		
17	Fiber patchcord, Duplex, LC-LC, 2m, 9/125µm	100		
18	Miscellaneous materials (conduits, information outlets, etc.)	1		
19	Labor, Installation, Testing, and Commissioning	1		
	Delivery Period 30 calendar days			

Procurement Mechanism to be used is "BY LOT"
ABC: PHP 16,501,350.00