



Republic of the Philippines
ILOILO SCIENCE AND TECHNOLOGY UNIVERSITY

La Paz, Iloilo City

• Trunkline: (033)320-7190 • Telefax: (033)329-4274

• Website: www.isatu.edu.ph



Section VII. Technical Specifications

ITEM NO.	SPECIFICATION	STATEMENT OF COMPLIANCE
	ABC (P 1,100,000.00)	[Bidders must state here either "Comply" or "Not Comply" against each of the individual parameters of each Specification stating the corresponding performance parameter of the equipment offered. Statements of "Comply" or "Not Comply" must be supported by evidence in a Bidders Bid and cross-referenced to that evidence. Evidence shall be in the form of manufacturer's un-amended sales literature, unconditional statements of specification and compliance issued by the manufacturer, samples, independent test data etc., as appropriate. A statement that is not supported by evidence or is subsequently found to be contradicted by the evidence presented will render the Bid under evaluation liable for rejection. A statement either in the Bidder's statement of compliance or the supporting evidence that is found to be false either during Bid evaluation, post-qualification or the execution of the Contract may be regarded as fraudulent and render the Bidder or supplier liable for prosecution.]

Procurement of PABX & CCTV Camera for VLE

ITEM NO.	Specification	UNIT	QTY	BRAND	Statement of Compliance
1	<p>PABX</p> <p>PABX Communication System (Dumangas) Main Unit PABX (Built in 6 C.O x 16 Locals) (1 unit) Dig. Phone 3 Line LCD, 24 CO keys, S-phone (1 pc) Basic Line Telephone (16 pcs) Cable for Backup Battery (1 pc) 12V 7.2AH Battery (3 units) Krone Lighting Arrester (1 set) S110 Block (1 set) Category 5e U/UTP, Outdoor, Installation Cable, Oil foam, 305m/ree, PE (5 rolls), Roughing-ins such as mouldings & other consumables (1 lot) Labor and Engineering Includes: Cabling Lay-out, Cable Pulling, Termination, Installation of Devices, Programming of Main Unit , Testing and Project Hand-over (1 lot)</p> <p>(Leon) Main Unit PABX (Built in 6 C.O x 16 Locals) (1 unit) Dig. Phone 3 Line LCD, 24 CO keys, S-phone (1 pc) Basic Line Telephone (16 pcs) Cable for Backup Battery (1 pc) 12V 7.2AH Battery (3 units) Krone Lighting Arrester (1 set) S110 Block (1 set) Category 5e U/UTP, Outdoor, Installation Cable, Oil foam, 305m/ree, PE (5 rolls), Roughing-ins such as mouldings & other consumables (1 lot) Labor and Engineering Includes: Cabling Lay-out, Cable Pulling, Termination, Installation of Devices, Programming of Main Unit , Testing and Project Hand-over (1 lot)</p>	lot	1		



Republic of the Philippines
ILOILO SCIENCE AND TECHNOLOGY UNIVERSITY
 La Paz, Iloilo City

• Trunkline: (033)320-7190 • Telefax: (033)329-4274
 • Website: www.isatu.edu.ph



		<p>(Barotac Nuevo) Main Unit PABX (Built in 6 C.O x 16 Locals)(1 unit) Panasonic Dig. Phone 3 Line LCD, 24 CO keys, S-phone (1 pc)Basic Line Telephone (16 pcs) Cable for Backup Battery (1 pc) 12V 7.2AH Panasonic Battery (3 units) Krone Lighting Arrester (1 set) S110 Block (1 set) Category 5e U/UTP, Outdoor, Installation Cable, Oil foam, 305m/ree, PE (4 rolls), Roughing-ins such as mouldings & other consumables (1 lot) Labor and Engineering Includes:Cabling Lay-out, Cable Pulling, Termination, Installation of Devices, Programming of Main Unit , Testing and Project Hand-over (1 lot)</p> <p>(Miagao) Basic Line Telephone (1 pc) CAT5E UTP Cable (100 m)</p> <p>Roughing-ins such as mouldings & other consumables (1 lot) Labor and Engineering Includes:Cabling Lay-out, Cable Pulling, Termination, Installation of Device, Programming for Additional Unit, Testing and Project Hand-over (1 lot)</p>			
2	CCTV Camera System	<p>Surveillance and Security system 4-ch Mini 1U 4K NVR (5 sets) 4 MP Fixed Bullet Network Camera (5 sets) 4 MP Fixed Dome Network Camera (5 sets) Storage: 1TB (5 pcs) 6-Port Unmanaged PoE Switch (5 pcs) 18.5" or higher WLED Monitor (5 pcs) Data Cable HDMI Cable M/M 15ft. (4.5M) (5 pcs)</p>	lot	1	



Republic of the Philippines
ILOILO SCIENCE AND TECHNOLOGY UNIVERSITY

La Paz, Iloilo City

• Trunkline: (033)320-7190 • Telefax: (033)329-4274
 • Website: www.isatu.edu.ph



	<p>7U wall cabinet with knots and bolts (5 sets) 625VA / 650 VA UPS (5 Units)</p> <p>Supply of local materials, Labor, Services and Configurations (1 lot): Supply and installation of PVC moulding / Flexible hose, Supply and installation of 10x20 m Cat 6 UTP patch cord (field terminated), Mounting of IP cameras & 7U wall mount cabinet</p> <p>Configuration Services: (Configuration of 5x NVR, Configuration of 10x Cameras, Connecting all cameras & manage to NVR, Walkthrough Training on Managing all Cameras & NVR Devices) for all 5 campuses</p>				
	Delivery Period: 30 days				
	Warranty 1 year				
